



# *KBS-3H*


## *- Development of the Horizontal Disposal Concept*

**SKB:** Erik Thurner, Stig Pettersson

**Saanio & Riekkola:** Margit Snellman, Jorma Autio

ESDRED, an EC project within the ongoing 6th R&D program:  
Engineering Studies and Demonstration of Repository Designs

# Horizontal emplacement, KBS-3H



# Motives for the KBS-3H concept

- **KBS-3H is estimated** to be a more efficient disposal method compared to KBS-3V
  - Reduction in rock excavation and backfilling
  - Less environmental impact during construction
  - Reduced costs
  - Reduced disturbance on the rock mass during construction and operation
- Quality aspects
  - Prefabricated disposal container enables an easier quality assurance of the canister near zone

# Key issues of the KBS-3H project

- Method for excavating the deposition drifts
- Methods for handling of ground water inflow into the drift
- Method for handling of super container in the drift
- Design of the bentonite buffer and the impact of groundwater inflow
- Consequences of the super container and other steel components
- Method for sealing the drift with an end plug
- Long term safety - Does KBS-3H fulfill the requirements with respect to long term safety?




# Main steps

- 2002            **Feasibility study of the concept**
- 2003            **Basic design**
- 2004-2005    **Technical development**
- 2006-2007    **Demonstration and testing**
- 2007            **Evaluation and reporting**

**Decision – Continuation of the project**

- 2008-            Programme under discussion

# Key components in the KBS-3H concept



# The KBS-3H concept

Unfortunatly the animation  
is not available

# Main objectives of the R&D studies


1. Repository layout and geological adaptation
2. Long-term safety
3. Demonstration and testing of the deposition equipment and drift components



# Main objectives of the R&D studies

- 1. Repository layout and geological adaptation**
2. Long-term safety
3. Demonstration and testing of the deposition equipment and drift components



# Repository layout of the KBS-3H concept



- About 30 super containers in a 300 m long drift
- Utilization degree depending on water inflow, bedrock conditions, etc
- Layout adaptation of the concept to Olkiluoto site

# Evaluation of drift components:

- Buffer and early evolution:
  - Bentonite studies
  - Design of distance block
- Ground water inflow:
  - Reduce water inflow by different methods




# Main objectives of the R&D studies

1. Repository layout and geological adaptation
- 2. Long-term safety**
3. Demonstration and testing of the deposition equipment and drift components

# Long-term safety

- Description of processes of importance in the 3H concept and analyses of the processes
- Description of the evolution of the 3H system. Interaction with Design and Demonstration to evaluate and resolve critical issues related to the early evolution.
- Perform radionuclide transport analyses
- Iron-bentonite interaction studies
- Preliminary Safety Case based on Olkiluoto site

# Processes and aspects of system evolution for 3H



# Main objectives of the R&D studies

1. Repository layout and geological adaptation
2. Long-term safety
- 3. Demonstration and testing of the deposition equipment and drift components**

# KBS-3H Demonstration at Äspö HRL

- Excavation of two drifts (February 2005)
- Test of the Deposition Equipment
- Full scale tests of drift components








# The deposition equipment




- Manufacturing is performed at CNIM in France
- SAT planned in September 2006
- Testing and demonstration of the equipment will be ongoing appr. 10 months
- Evaluation and reporting up to autumn 2007

# Test of drift components



# Conclusions

- **Important phase**
  - Main activities are well advanced or completed
  - Some issues have still to be solved
  - Demonstration and testing
  - Evaluation and reporting
- **KBS-3H feasible alternative to 3V concept?**
  - Stepwise approach
  - Planning of further development work



# End of presentation!

## Questions?